



www.module-t.com
info@module-t.com

MODULAR CONTAINER

Our sandwich panel demounted container are insulated in rock wool or in poliurethane with a minimal thickness of 50mm. Steel sheet and frame are galvanized and painted. Standard setup contains one steel door and two PVC windows. Electrical equipments and lighting system are included.

Our modular demounted container are specially made for export. The exclusive Module-T packaging technology minimizes ground and sea transport costs, while protecting the good from any impacts that may occur during the transport.

-10 standard units of 6 meters are delivered in one maritime container of 40'.

-5 standard units of 12 meters are delivered in one maritime container of 40'.

ROCK WOOL OR POLIURETHANE INSULATION (MINIMUM 50MM)

QUICK ASSEMBLY

EASY TO MOVE

OPTIMIZED LOGISTIC

UXTAPOSITION (OPTION)

SUPERPOSITION (OPTION)

SETUP ON DEMAND



INSULATION



GALV.
PAINTED AND GALVANIZED STEEL SHEET AND FRAM



(HOOK) LIFTING



OPTIMAL PACKAGING



OUTLETS



LIGHTING (ROUND OR FLUORESCENT)



LOCATION FOR A/C



GALVANIZED AND PAINTED STEEL DOOR



DOUBLE-GLAZED



SUPPORTED ON CONCRETE PLINTHS



SANITARY (OPTION)



DOOR/WINDOW BARS (OPTION)



ALU
ALUMINIUM DOOR/WINDOW (OPTION)



SPECIAL STORAGE HEAVY LOAD (OPTION)



PHONE PLUG (OPTION)



FURNITURE (OPTION)



- 1 Hook lifting
- 2 Sanitary container (Shower, WC, Sink, fitting room)
- 3 Container with furniture (furniture on demand)
- 4 Special packaging – Transport position per maritime container
- 5 Production in series or customized.



www.module-t.com
info@module-t.com

MODULAR BUILDING

The sandwich panel containers can be used in order to build modular buildings by juxtaposing and superimposing the containers.

JUXTAPOSITION: The standard sandwich panel containers of 6,00 x 2,40 meters can be juxtaposed along the length (design of a 6,00 x 2,40 meters container with two standard modular demounted containers), or width (design of a 12,00 x 2,40 meters container with two standard modular demounted containers). In order to juxtapose the containers, Module-T will provide the Pack of Juxtaposition option which contains connection and insulation elements which meet the configuration desired by the customer.

SUPERPOSITION: The sandwich panel containers with reinforced structure can be superimposed according to the needs of the customer. For the superposition, Module-T will provide the Pack of Superposition option adapted to the customer project, the access elements to the floor will be quickly installed on site without any welding (reinforced chassis, access staircase, guardrails, passageways).



JUXTAPOSITION PACK



SUPERPOSITION PACK



ROOFING PACK



GREEN PACK

THE ULTIMATE MODULAR DEMOUNTED CONTAINER: STACKABLE AND JUXTAPOSABLE





www.module-t.com
info@module-t.com

PREFABRICATED STEEL BUILDING

Prefabricated Module-T system in galvanized steel structure allows for building high quality and sustainable buildings. This system is especially made for facilitate the assembly and disassembly of the sustainable or temporary building. All architectural and statistics calculations are made by our technical department.

Fast

- Quick assembly – Easy to remove and install in new area
- Pre-industrialised, very short period building site

Economic

- Excellent quality/price level
- Cheaper than the traditional construction

Customizable

- External covering - roofing
- Adjustment to your imperative interior design
- Wide selection of optional equipments

Environmental compliance

- Prefabricated in factory, no waste in the construction site.



ECOLOGICAL
STANDARDS



PAINTED AND
GALVANIZED STEEL SHEET
AND FRAM

